KADUR DIVISION.

Dated 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Execut Engineer, Kadur Division, up to 1 P.M., on 30th September 1930, for constructing Chattram, (2) Veterinary Hospital and three blocks of officials' quarters at Kalasa, Mudg Taluk. An approximate estimate of quantities is given below. These quantities are guaranteed. The work should be completed by the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engine Office at Chikmagalur, between the hours of 11-30 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from Executive Engineer. The tenders should be accompanied by a statement in the form gi below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Governm Promissory Notes as earnest money and be superscribed "Tender for constructing (1) Chattram, (2) Veterinary Hospital and three blocks of officials' quarters at Kalasa, Mudg Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer and Ch Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to ass any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will required to execute the usual contract bond; in default of which, his tender will be consider cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will posted on the notice board in the Executive Engineer's Office in due course. No enqui regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will returned.

9. Rates should be noted for each item of work.

10. Percentage quotations, either below the lowest tender or sanctioned estimat amount will not be accepted.

11. The contract must not be sub-let.

12. No claims for enhanced rates will be preferred of tender and during the course execution of work.

13. In all matters of dispute regarding quality of work, rates, etc., the decision of th Superintending Engineer, Shimoga Circle, is final and legally binding.

Approximate quantities for constructing the above buildings.

Approximate quantities for constructing a Chattram at Kalasa, Mudgere Taluk.

Serial No.	Particulars of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
1	Earthwork excavation and filling in basement including watering, etc.	C.yd.	61		
2	Stone jelly concrete in chunam mortar ...	C.ft.	668		
3	Rough stone in mud foundation and basement	"	1,327		
4	Burnt brick in mud superstructure ...	"	1,983		
5	Burnt brick in mortar	"	524		
6	Burnt stone slabs 4½" to 6" dressed ..	S.ft.	137		
7	Nandiwood wrought and put up including wood oiling.	C.ft.	127·18		
8	Nandiwood battened door with double shutters 1" thick including frame, iron fitting, etc.	S.ft.	117		
9	Nandiwood battened windows with double shutters including iron bars fittings	"	144		

Serial No.	Particulars of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
15	Providing and fixing 1st Class Mangalore ridge tiles set in mortar including cement pointing.	R.ft.	132		
16	Flooring with 3" gravel including lead, watering, tamping and cowdung wash.	Sqr.	9·00		
17	Providing and fixing Nandi wood eave board (plain) 9" long including wood oiling	R.ft.	242		
18	Clearing site, brick bonds over roof at ends and unforeseen items.	Lumpsum			
19	Zinc sheet and teak plank for valleys with cement border at top, plastering, etc., complete.	R.ft.	29		

Approximate quantities for constructing a Veterinary Hospital at Kalasa, Mudgere Taluk.

				Rs. a. p.	
1	Earthwork excavation and filling in basement	C.yd.	41		
2	Stone jelly concrete in chunam mortars ...	C.ft.	494		
3	Rough stone in mud foundation and basement.	"	868		
4	Burnt brick in mud superstructure	"	1,581		
5	Nandiwood battened door with double shutters 1" thick, iron fittings, etc., complete.	S.ft	91		
6	Nandi wood battened windows with double shutters, panelled outside and glazed inside with iron bars, hinges, etc., complete.	"	56		
7	Nandi wood gate including iron fittings, etc., complete.	No.	1		
8	Burnt stone slabs dressed 6" thick roughly dressed.	S ft.	115		
9	Burnt stone slab pillars (6" x 1') nicely dressed and champered at edges.	No.	4		
10	Cutting grooves in stone pillars	"	4		
11	Nandi wood wrought and put up including wood oiling.	C.ft	72·76		
12	Roofing with 1st Class Mangalore tiles on 1" teak reepers including nailing, etc.	Sqr.	12·50		
13	Silicate painting two coats ...	"	3·69		
14	Chunam plastering two coats ...	"	31·65		
15	Providing 1st Class Mangalore ridge tiles including fixing in mortar and cement pointing.	R.ft.	88		
16	Cement pointing to basement ...	Sqr.	2·76		
17	Whitewashing two coats ...	Sqr.	31·65		
18	Burnt brick in mortar coping 1½' thick over compound wall including plastering.	R.ft.	54		
19	Flooring with 1st Class Mangalore tiles on 3" concrete including cement pointing.	Sqr.	3·69		
20	Gravel flooring consolidated including lead and cowdung wash.	"	3·69		
21	Clearing site, etc. ...	Lumpsum			
22	Cornice 9"	R.ft.	26		
23	Honne wood eave board plain including chacolate painting.	"	101		
24	Jambs of doors and windows in burnt brick in mortar and unforeseen items.	Lumpsum			
25	Water trough, complete ...	Lumpsum			

Constructing three blocks of quarters at Kalasa, Mudgere Taluk.

Serial No.	Particulars of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
1	Earthwork excavation for foundation and filling basement gravelly soil.	C.yd.	29		
2	Stone jelly concrete in chunam mortar ...	C.ft.	350		
3	Rough stone in mud with 3¾ mile lead for stones.	C.yd.	755		
4	Burnt brick in mud with bonds, etc., as per specification of mariots.	C.ft.	954		
5	Burnt brick in mortar	„	267		
6	Burnt stone slabs 4" thick roughly dressed and fixed.	S.ft.	74		
7	Honne or matti battened doors with frame hinges bolts, etc., complete.	„	108		
8	Honne or matti wood battened windows with frame iron bars, hinges, screws, etc., complete.	„	9		
9	Honne wood or matti battened ventilators with frame iron bars with swaying arrangements cotton rope, etc., complete.	„	19		
10	Chunam plastering two coats ...	Sqr.	24·00		
11	Nandi or matti wood wrought and put up including wood oiling.	C.ft.	62·82		
12	Roofing with 1st Class Mangalore tiles in teak reepers 1" x 1½".	Sqr.	11·46		
13	Mangalore ridge tiles set in mortar and cement pointed.	R.ft.	89		
14	Flooring with 1st Class Mangalore tiles on 3" concrete bed with cement pointing	Sqr.	3·53		
15	Flooring with Cuddapa slabs 1½" thick on 3" concrete bed including cement pointing.	„	1·03		
16	Burnt stone pillars nicely dressed ...	S.ft.	32		
17	Cutting grooves in pillars	No.	4		
18	White washing two coats	Sqr.	22·69		
19	Chunam pointing	„	1·67		
20	Providing wall shelves on pegs with jungle wood planks.	S.ft.	18		
21	Providing links ...	No.	1		
22	Providing mortar and pestle ...	„	1		
23	Painting doors with chacolate painting two coats and wood oiling inside.	Sqr.	3·11		
24	Constructing latrine complete ...	L. S.	5·00		
25	Tarring to wood work ...	L. S. Sqs.	5·00		
26	Clearing site and levelling ground ...	L. S.			
27	Coping over with compound wall with plastering, complete.	R.ft.	22		
28	Honney wood eave board including chocolate painting.	„	61		

K. RAMASESHAN,
For *Executive Engineer.*

SHIMOGA DIVISION.

Notification dated 10th September 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 10th October 1931, for restoring Israpur Balekatte Tank, Reg. No. 48, Honnali Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M.